## UNSURFACED MEDIANS, UNSURFACED ROADWAYS, ROADSIDE STRIPS, OR EASEMENTS **SURFACED STREETS OR SURFACED EASEMENTS** SURFACING (EXCLUDING **GRAVEL ROADS)** BACKFILL COMPACTED TO BASE MATERIAL AND SUBGRADE, 90% RELATIVE COMPACTION COMPACTED TO 95% RELATIVE COMPACTION. (MAXIMUM LIFT THICKNESS IS 6 INCHES). **BACKFILL COMPACTED** 2TO 90% RELATIVE COMPACTION. MAXIMUM LIFT 2 12" 12" THICKNESS IS 2 FEET. REPLACE STRUCTURAL SECTION AS FOLLOWS: VARIABLE VARIABLE Ш $\sqrt{3}$ SURFACING - EXISTING THICKNESS PLUS 1" (IN) OR 3" (IN) MINIMUM. BEDDING TO BE PER MANUFACTURER'S RECOMMENDATIONS AND PER BASE - SAME TYPE AND THICKNESS AS EXISTING BASE MATERIAL, $4^{\prime\prime}$ (IN) MIN OR AS SPECIFIED. STD DWG SB-157. HIGH GROUND WATER CONDITION SEE NOTE 2 I. STRUCTURAL ZONE II. INTERMEDIATE ZONE III. PIPE AND UTILITY ZONE NOTE: 3 **CLEARANCE "A"** 1. WHEN A FIRM FOUNDATION IS NOT ENCOUNTERED, DUE TO SOFT, SPONGY, OR OTHER UNSUITABLE MATERIAL, SUCH MATERIAL SHALL BE REMOVED TO THE LIMITS DIRECTED BY THE ENGINEER, AND THE RESULTING EXCAVATION BACK FILLED WITH PIPE BEDDING 1. CLAY PIPE: SEE STD. DWG. SB-159 MATERIAL COMPACTED TO 90% RELATIVE COMPACTION. 2. PLASTIC PIPE: PIPE SIZES THROUGH 12"- "A"=6"-9" \* 2. WHEN HIGH GROUND WATER CONDITION EXISTS, OVER EXCAVATE AND INSTALL ADDITIONAL BEDDING WITH GEOFABRIC. PIPE SIZES OVER 12"- "A"=1'-0" MIN. OVER EXCAVATE MINIMUM OF 2-FEET, 2-INCH TO 3-INCH ROCK, 95% COMPACTED. GEOFABRIC WRAP WITH 12-INCH MINIMUM OVERLAP AT TOP PER SPECIFICATIONS. EASTERN MUNICIPAL WATER DISTRICT STANDARD DRAWING

DIRECTOR OF ENGINEERING

		REVISIONS					APPROVALS			
	NO.	DATE	INITIAL	DESCRIPTION	APP'D	DATE		INITIAL	DATE	
	<u>(A</u>	9/25/20	GS	UPDATED TITLE BLOCK, FONT, LOGO, ADDED NOTE 2 AND BEDDING	AGA	9/25/20	DESIGN			
	<u>\</u>	10/15/03	СМ	REVISED COMPACTION REQUIREMENT	VJB	10/15/03	CONSTRUCTION			
	4	2/19/97	KER	REV'D TO INCLUDE ALL PREVIOUS REVISIONS	VJB	7/28/97	INSPECTION			emw
	3	7/11/95	KER	REV'D TO COMPLY W/CURRENT GREEN BOOK	VJB	7/13/95	OPERATIONS			
	2	1/31/95	KER	ADDED PIPE TO TRENCH CLEARANCE REQ	VJB	2/3/95	SUBMITTED	VJB	3/1/93	
	***************************************			SCALE: NONE		RECOMMENDED Joseph D. Van Sickle				
				DRAWN BY: KER						



3/5/93

DATE

## TRENCH BACKFILLFOR SEWER PIPE

APPROVED William E. Plummer
ASSISTANT GENERAL MANAGER

SB-158

3/8/93